

**SCHOOL OF OPEN LEARNING
CAMPUS OF OPEN LEARNING
UNIVERSITY OF DELHI
DELHI – 110007**

Sub: Providing Kota stone flooring and glazed tiles on wall in R.No.10 & veranda at South Study Centre, South Moti Bagh.

Sealed quotations are hereby invited from the working contractors enlisted with CPWD /Railway/MES/Delhi University for the above mentioned work so as to reach the undersigned by 3.00 p.m. on 24/09/15 (Extended Date). Blank quotation form can be obtained from the General Section, Room No. 206, School of Open Learning, University of Delhi or downloaded from SOL/DU website www.sol.du.ac.in or www.du.ac.in up to 24/09/15(Extended Date) by 1 p.m. and quotations will be opened on 28/09/15 at 10.00 a.m.

The details of items:-

- | | | | | |
|-------------------|---|----------|-------|-----|
| Item No. 1 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Monitoring Committee.
Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) | 10.00 M3 | @ Rs. | Rs. |
| Item No. 2 | Kota stone slab flooring over 25 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick | 95.00 M2 | @ Rs. | Rs. |
| Item No. 3 | Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Monitoring Committee, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete. P/F 1st quality ceramic glazed wall tiles over 12 mm thick bed of cement Mortar (1:3). | 95.00 M2 | @ Rs. | Rs. |
| Item No.4 | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Monitoring Committee, beyond 500 m initial lead, for all leads including all lifts involved. | 20.00 M3 | @ Rs. | Rs. |

Terms and Conditions:

1. Work should be completed within one month.
2. C.P.W.D specification will be followed strictly.
3. Undersigned reserves the right to reject any or all quotation without assigning any reason.
4. Should the work be not completed to the satisfaction of the SOL within the stipulated period, the Contractor shall be bound to pay to the SOL, a sum calculated @ 0.5% of the Contract value for per week of delay subject to a maximum of 10% of the contract value by way of liquidated damages during which time the work remains uncommenced or unfinished after expiry of completion date.
5. Rates should be quoted both in words and figures.
6. The Contractor should visit the site before quoted their rates.
7. The site shall be cleared of all loose material.
8. The contractor or his representative should be made available at the work site during the execution of the work.
9. Water/electricity required for the work will be allowed to the contractor for use and 1.5% of the full cost of the work executed, will be recovered
10. The contractor shall have to get the site of work cleared during execution and / or on completion of work as per directions and to the satisfaction of the committee/SOL authority.
11. Sample of the material should be approved from the Monitoring Committee before using at site.

Signature _____

Name of Contractor _____

Address _____

Phone No. /Mobile No. _____

PAN No. _____

VAT No. _____

Bank Account Number _____

IFSC Code of the Bank _____

Name & Address of Bank _____

ASSISTANT REGISTRAR
(General) Offtg.