

**SCHOOL OF OPEN LEARNING
CAMPUS OF OPEN LEARNING
UNIVERSITY OF DELHI
DELHI – 110007**

Sub: Repairing of street lights in the premises of SOL (North) University of Delhi.

Sealed quotations are hereby invited from the working contractors enlisted with CPWD /Railway/MES/Delhi University for the above mentioned work so as to reach the undersigned by 3.00 p.m. on 26/11/15. Blank quotation form can be obtained from the General Section, Room No. 206, School of Open Learning, University of Delhi or downloaded from SOL/DU website www.sol.du.ac.in or www.du.ac.in up to 26/11/15 by 1 p.m. and quotations will be opened on 26/11/15 at 4.00 p.m.

The details of items:-

Item no.1	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit as required. 2 x 4 sq. mm	250 mtr.	@ Rs.	Rs.
Item no.2	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	18 Nos.	@ Rs.	Rs.
Item no.3	Supplying and fixing 4 x 25 sq mm of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of following size on wall surface as required. (clamped with 1mm thick saddle)	150 mtr.	@ Rs.	Rs.
Item no.4 7.3.1	Supplying and Laying of one number 4 x 25 sq mm PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as reqd, including sand cushioning and protective covering etc as reqd.	270 mtr.	@ Rs.	Rs.
Item no.5	Supplying and fixing following material for repairing/maintaining the existing street light fitting etc. as reqd.			
	(a) Ignature suitable for 250 watt street light fitting/HPSV Lamps	4 Nos.	@ Rs.	Rs.
	(b) Copper suitable blast for 250 watt street light fitting/HPSV Lamp	4 Nos.	@ Rs.	Rs.
	(c) HPSV Lamp (White) 250 watts suitable for existing street light fitting 250 watt	15 Nos.	@ Rs.	Rs.

Item no.6 Removing the existing aluminium paint by burner, scraping sand papering and preparing the surface smooth by using M.S putty on the existing street light poles (height up to 20') and painting with Aluminium paint. The existing M.S box should be painted and repaired by refixing cover/missing items etc. as reqd. at site i/c testing/checking the existing earthing connection/earthing pit and making good the same.

18 Nos.

@ Rs.

Rs.

Terms and Conditions:

1. Work should be completed within 45 days.
2. C.P.W.D specification will be followed strictly.
3. Undersigned reserves the right to reject any or all quotation without assigning any reason.
4. Should the work be not completed to the satisfaction of the SOL within the stipulated period, the Contractor shall be bound to pay to the SOL, a sum calculated @ 0.5% of the Contract value for per week of delay subject to a maximum of 10% of the contract value by way of liquidated damages during which time the work remains uncommenced or unfinished after expiry of completion date.
5. Rates should be quoted both in words and figures.
6. The Contractor should visit the site before quoted their rates.
7. The contractor or his representative should be made available at the work site during the execution of the work.
8. The contractor shall have to get the site of work cleared during execution and / or on completion of work as per directions and to the satisfaction of the committee/SOL authority.
9. Sample of the material should be approved from the Monitoring Committee before using at site.

Signature _____

Name of Contractor _____

Address _____

Phone No. /Mobile No. _____

PAN No. _____

VAT No. _____

Bank Account Number _____

IFSC Code of the Bank _____

Name & Address of Bank _____

**ASSISTANT REGISTRAR
(General) Offtg.**