

**SCHOOL OF OPEN LEARNING
CAMPUS OF OPEN LEARNING
UNIVERSITY OF DELHI
DELHI – 110007**

Sub: Repairing of main entrance gate of South Study Centre, South Moti Bagh, SOL, University of Delhi

Sealed quotations are hereby invited from the working contractors enlisted with CPWD /Railway/MES/Delhi University for the above mentioned work so as to reach the undersigned by 3.00 p.m. on 17/11/15. Blank quotation form can be obtained from the General Section, Room No. 206, School of Open Learning, University of Delhi or downloaded from SOL/DU website www.sol.du.ac.in or www.du.ac.in up to 17/11/15 by 1 p.m. and quotations will be opened on 17/11/15 at 4.00 p.m.

The details of items:-

Item no-1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	100.00 M2	@ Rs.	Rs.
Item no-2	Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	06.00 M3	@ Rs.	Rs.
Item no-3	Granite Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and cement slurry @ 3.3 kg/sqm including pointing in white cement complete. Granite of any colour and shade	20.00 M2	@ Rs.	Rs.
Item no-4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (MS sheet in door/gate will be welded)	200.00 Kg	@ Rs.	Rs.
Item no-5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	50.00 sqm	@ Rs.	Rs.
Item no-6	Repairing of main iron gate by removing existing paint, rusts by proper arrangement finishing proper by applying M.S. putting as and where required etc as reqd.	20.00 sqm	@ Rs.	Rs.

Item no-7 Repairing the existing channel gate/collapsible gate by welding with priming painting i/c providing/fixing the missing parts of channel gates etc. as reqd. The repairing work will be completed after removing the existing channel gate and refixing the same after repairing/painting etc.

2 Nos.

@ Rs.

Rs.

Item no-8 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand) i/c satana line wash et as reqd.

100.00 sqm.

@ Rs.

Rs.

Terms and Conditions:

1. Work should be completed within one month.
2. C.P.W.D specification will be followed strictly.
3. Undersigned reserves the right to reject any or all quotation without assigning any reason.
4. Should the work be not completed to the satisfaction of the SOL within the stipulated period, the Contractor shall be bound to pay to the SOL, a sum calculated @ 0.5% of the Contract value for per week of delay subject to a maximum of 10% of the contract value by way of liquidated damages during which time the work remains uncommenced or unfinished after expiry of completion date.
5. Rates should be quoted both in words and figures.
6. The Contractor should visit the site before quoted their rates.
7. The contractor or his representative should be made available at the work site during the execution of the work.
8. Water/electricity required for the work will be allowed to the contractor for use and 1.5% of the full cost of the work executed, will be recovered
9. The contractor shall have to get the site of work cleared during execution and / or on completion of work as per directions and to the satisfaction of the committee/SOL authority.
10. Sample of the material should be approved from the Monitoring Committee before using at site.

Signature _____

Name of Contractor _____

Address _____

Phone No. /Mobile No. _____

PAN No. _____

VAT No. _____

Bank Account Number _____

IFSC Code of the Bank _____

Name & Address of Bank _____

**ASSISTANT REGISTRAR
(General) Offtg.**