

**SCHOOL OF OPEN LEARNING
CAMPUS OF OPEN LEARNING
UNIVERSITY OF DELHI
DELHI – 110007**

**Sub: Providing shed for RO plant at terrace of new admin block of SOL,
University of Delhi.**

Sealed quotations are hereby invited from the working contractors enlisted with CPWD /Railway/MES/Delhi University for the above mentioned work so as to reach the undersigned by 3.00 p.m. on 16/11/15. Blank quotation form can be obtained from the General Section, Room No. 206, School of Open Learning, University of Delhi or downloaded from SOL/DU website www.sol.du.ac.in or www.du.ac.in up to 16/11/15 by 1 p.m. The quotations will be opened on 16/11/15 at 4.00 p.m.

The details of items:-

Item No. 1 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)

10.00 M3 @ Rs. Rs.

Item No. 2 15 mm cement plaster on the rough side of single or half brick wall of mix: 1:4 (1 cement: 4 fine sand)

100.00 M2 @ Rs. Rs.

Item No. 3 Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.

30.00 M2 @ Rs. Rs.

Item No. 4 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes

150.00 kg @ Rs. Rs.

Contd.....2/-

Item No. 5	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D, F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment). Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	300.00 kg	@ Rs.	Rs.
Item No. 6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.00 M3	@ Rs.	Rs.
Item No. 7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	1.00 M3	@ Rs.	Rs.
Item No. 8	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	15.00 M2	@ Rs.	Rs.
Item No. 9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Cold twisted bars	100.00 kg	@ Rs.	Rs.
Item No. 10	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	75.00 M3	@ Rs.	Rs.
Item No. 11	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water tinnable priming coat with cement primer	75.00 M2	@ Rs.	Rs.

Item No. 12	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	20.00 M2	@ Rs.	Rs.
Item No. 13	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase	10.00 Mtr.	@ Rs.	Rs.
Item No. 14	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	10.00 Mtr.	@ Rs.	Rs.
Item No. 15	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0 mm thick glass panes	10.00 M2	@ Rs.	Rs.
Item No. 16	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	10.00 M2	@ Rs.	Rs.
Item No. 17	Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40 mm wide and 4 mm thick	20.00 Mtr.	@ Rs.	Rs.
Item No. 18	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	10.00 M3	@ Rs.	Rs.

Terms and Conditions:

1. Work should be completed within one month.
2. C.P.W.D specification will be followed strictly.
3. Undersigned reserves the right to reject any or all quotation without assigning any reason.
4. Should the work be not completed to the satisfaction of the SOL within the stipulated period, the Contractor shall be bound to pay to the SOL, a sum calculated @ 0.5% of the Contract value for per week of delay subject to a maximum of 10% of the contract value by way of liquidated damages during which time the work remains uncommenced or unfinished after expiry of completion date.
5. Rates should be quoted both in words and figures.
6. The Contractor should visit the site before quoted their rates.
7. The contractor or his representative should be made available at the work site during the execution of the work.
8. Water/electricity required for the work will be allowed to the contractor for use and 1.5% of the full cost of the work executed, will be recovered
9. The contractor shall have to get the site of work cleared during execution and / or on completion of work as per directions and to the satisfaction of the committee/SOL authority.
10. Sample of the material should be approved from the Monitoring Committee before using at site.

Signature _____

Name of Contractor _____

Address _____

Phone No. /Mobile No. _____

PAN No. _____

VAT No. _____

Bank Account Number _____

IFSC Code of the Bank _____

Name & Address of Bank _____

ASSISTANT REGISTRAR
(General) Offtg.